



Bulletin

Engineering Department - Land Development

Issue Date: July 18, 2011

Reference No. 5250-20 (Bulletin)

AUTHORITY: GENERAL MANAGER, ENGINEERING

ATTENTION: LAND DEVELOPMENT CONTRACTORS AND CONSULTANTS

SUBJECT: MANHOLE FRAME AND CONCRETE DONUT

REMINDER TO CONTRACTORS:

MMCD (Gold Edition)

Section 02725 3.3

- .12** Set frames by firmly embedding in mortar on a minimum of 1, maximum of 3 courses of bricks or precast concrete riser rings, or cast-in-place form system with due regard to maximum distance to the first step.
- .13** Grout inside and outside and between courses of bricks or grade rings with mortar to ensure neat even finish.

MMCD Drawing S1

- Maximum depth to first rung is 500mm.

Please be advised that the above standard is to be followed and the City will not permit rungs to be installed in the area between the donut casting and the manhole frame.

STEPHEN TAYLOR, CPWI 3
Acting Inspection Services Manager