



## PROCUREMENT SERVICES

CITY OF SURREY, SURREY CITY HALL  
13450 – 104 Avenue, Surrey, B.C., V3T 1V8  
Tel: 604-590-7274  
E-mail: [purchasing@surrey.ca](mailto:purchasing@surrey.ca)

### ADDENDUM No. 2

---

REQUEST FOR QUOTATION No.: 1220-040-2021-058

TITLE: ARENA RELIEF PIPING UPGRADES & SECONDARY  
COOLANT UPGRADES

ADDENDUM ISSUE DATE: SEPTEMBER 22, 2021

**REVISED CLOSING DATE: SEPTEMBER 28, 2021**

---

### INFORMATION FOR CONTRACTORS

Contractors are advised that Addendum No. 2 to 1220-040-2021-058 is hereby issued by the City. This addendum shall form part of the contract documents and is to be read, interpreted and coordinated with all other parts. The following information is provided to answer questions raised by Contractors for the above-named project, to the extent referenced and shall become a part thereof. No consideration will be allowed for extras due to the Contractors or any sub-contractor not being familiar with this addendum. This Addendum No. 2 contains two (2) pages.

### QUESTION AND ANSWER:

- Q1. Please confirm that the removal of the NH3 fire line at the Bridgeview Arena is included in the scope of work?
- A1. The fire line at North Surrey Sport & Ice Complex is to be removed.**
- Q2. We assume the existing fireboxes are to remain in place to house the existing emergency shut off switches. Please confirm.
- A2. The existing fire box is to be removed and disposed of. A new, smaller, custom-made fire box with the emergency shutdown switch is to be installed with a lockable cover. The new fire box and wall behind the new box must be repainted to match the new relief line and the existing wall.**
- Q3. The Watts secondary relief valves do not have a fluid flow rating. Please confirm that secondary relief valves with a true fluid flow rating are to be provided.

- A3. The relief valve for the secondary relief system must be sized for liquids. The refrigeration contractor is to provide relief valve calculations for each arena as required by the TSB to meet the code upgrade requirements. These calculations must be reviewed and stamped by a professional engineer.**

**The refrigeration contractor must provide relief line calculations for the new relief lines being installed.**

---

**All Addenda will become part of the Contract Documents.**

---

**- END OF ADDENDUM -**