



PROCUREMENT SERVICES

CITY OF SURREY, SURREY CITY HALL
13450 – 104 Avenue, Surrey, B.C., V3T 1V8
Tel: 604-590-7274
E-mail: purchasing@surrey.ca

ADDENDUM No. 6

REQUEST FOR QUOTATION No.: 1220-040-2021-061

TITLE: SOUTH SURREY INDIGENOUS CARVING CENTRE

ADDENDUM ISSUE DATE: DECEMBER 16, 2021

(REVISED) DATE: PREFER TO RECEIVE QUOTATIONS ON OR BEFORE DECEMBER 16, 2021

INFORMATION FOR CONTRACTORS

Contractors are advised that Addendum No. 6 to 1220-040-2021-061 is hereby issued by the City. This addendum shall form part of the contract documents and is to be read, interpreted and coordinated with all other parts. The following information is provided to answer questions raised by Contractors for the above-named project, to the extent referenced and shall become a part thereof. No consideration will be allowed for extras due to the Contractors or any sub-contractor not being familiar with this addendum. This Addendum No. 6 contains two (2) pages.

QUESTIONS AND ANSWERS:

Q1. Addendum 4: Some of the answers state that the changes will be addressed in “IFT documentation” However, after going on the FTP Site, we’ve noticed the IFT drawings are the original, published on November 4th, 2021. Is that normal as we are confused?

A1. The change was confirmed or explained in the tender response and drawing changes will be addressed in issued for construction (IFC) – documentation.

Q2. Refer to: Addendum 2 (Q&A 13) says to provide separate prices to allow for 25% and 100% screening of excavated material.

Refer to: Addendum 5 (Q&A 27 & 31) says screening above 10% will be done by change order.

Are separate prices for 25 & 100% screening still required?

A2. Refer to Addendum 2, Q&A 12-13 as in the screen shot below. Delete the last line in A13.:

Screen Shot:

Q12. As for the archaeological requirements, will every bucket of earth out of the ground for the electrical trenches need to be inspected?

A12. The electrical trench needs to be monitored while it is being dug. The soil could be investigated by rake as the trench progresses. Allow for 10% screening or raking by the archaeological field director.

Q13. Same question (as Q12.) for (regarding) the foundation?

A13. The excavation for the foundation will need to be monitored. Allow for 10% screening or raking by the archaeological field director.

The level of screening for Q12 and Q13 may change during excavation, this will be at the discretion of the archaeological field director. Provide separate prices for 25% and 100% screening during excavation.

Q3. The addendum 2 asks that all exterior wood panels are Western Red Cedar with semitransparent finish on all sides!

I presume we are talking about the 19mm plywood panels installed in between the 38mm x 89mm vertical lumber pieces. If this is the case, then what type of wood is expected for the balance of the lumber?

A3. All secondary wood framing elements should be "No. 2 or better clear western red cedar".

Q4. Is there any specific finish requirement for the balance of the lumber at the perimeter wall?

A4. All primary structural and secondary framing elements to receive semi-transparent finish as selected by the architect.

All Addenda will become part of the Contract Documents.

- END OF ADDENDUM -