



PROCUREMENT SERVICES

CITY OF SURREY, SURREY CITY HALL
13450 – 104 Avenue, Surrey, B.C. V3T 1V8
Tel: 604-590-7274
E-mail: purchasing@surrey.ca

ADDENDUM No. 2

REQUEST FOR QUOTATION No.: 1220-040-2022-044

TITLE: CLOVERDALE STETSON BOWL – BLEACHER
UPGRADES

ADDENDUM ISSUE DATE: MAY 30, 2022

**REVISED DATE: PREFER TO RECEIVE SUBMISSION ON OR
BEFORE JUNE 2, 2022.**

INFORMATION FOR CONTRACTORS

Contractors are advised that Addendum No. 2 to 1220-040-2022-044 is hereby issued by the City. This addendum shall form part of the contract documents and is to be read, interpreted and coordinated with all other parts. The following information is provided to answer questions raised by Contractors for the above-named project, to the extent referenced and shall become a part thereof. No consideration will be allowed for extras due to the Contractors or any sub-contractor not being familiar with this addendum. This Addendum No. 2 contains two (2) pages.

CLARIFICATION:

1. Inspections of the remedial work for this project, including inspections of the scaffolding, will be conducted by Element Consulting Engineers, on behalf of the City of Surrey. Therefore, Contractor's Quotations should not include the cost of engineering for inspections.

QUESTIONS AND ANSWERS:

Q1. Will onsite washroom be provided?

A1. No onsite washroom provided; Contractor may bring in a portable washroom which must be kept within the secure fencing area.

Q2. Will onsite power be provided?

A2. 120V power is accessible in the locked storage room behind the North bleachers. Access to be provided.

Q3. Will temporary fencing already on site be kept in place or will we need to provide our own?

A3. Existing fencing to remain for duration of bleacher work.

- Q.4** Do the notes indicating the individual board quantities account for all boards to be replaced?
- A4.** As per Addendum No. 1, A5: The Tables for “Individual Seat and Floorboard Removal and/or Replacement” on Drawings 1.1 and 2.1 refer to boards over and above any other areas bubbled and indicated on the Drawings as needing removal and/or replacement. The boards referred to in the Tables are randomly located and have been physically marked and identified onsite with marking paint.
- Q5.** Drawing S-2287-2.5 shows seats are 2x6 however on-site measurement shows seats are 2x10. Could you reconfirm other measurements (ledgers, supports, bracing, etc.).
- A5.** All seat boards and floorboards are to be 2x10. For remaining members, measurements are as shown in the Drawing.
- Q6.** Could you provide a fastening detail?
- A6.** All seat and floorboard replacements shall be fastened, as follows:
- Wood (2x) to wood connections shall be fastened with 3” Simpson SDWS Timber Screws (exterior grade)
 - Wood to metal connections shall be fastened with #12 x 2” hot-dipped galvanized Tek screws
 - For example, seat board connections to double angle top chords of trusses.

All Addenda will become part of the Contract Documents.

- END OF ADDENDUM -